



**REQUEST FOR QUOTATION ON
CONSTRUCTION OF CONCRETE FORKLIFT
WALKWAY PAVEMENT**

LOCATION: ABA MILL

DATE ISSUED: JANUARY 09, 2023

**BIDS ARE TO BE SUBMITTED ON
OR BEFORE 11 AM - FRIDAY
13TH JANUARY 2022.**

TO ALL INTERESTED VENDOR

SPECIFICATION

- **BID IS EXPECTED FOR THE CONSTRUCTION OF A FORKLIFT WALKWAY FROM WEIGHBRIDGE TO THE SILO ENVIRONMENT.**
- **PAVEMENT LENGTH, WIDTH AND THICKNESS ARE EXPECTED TO BE 50m x 3m x 0.23m RESPECTIVELY. BASE HARDCORE OF 0.12m IS TO BE PROVIDED FOR.**
- **PAVEMENT CASTING AGGREGATE IS TO BE MADE IN THE RATIO 1:1.5:3. MEASURE OF HARDENER TO ENSURE CONCRETE CURE WITHIN 7 DAYS IS TO BE ADDED TO THE MIX.**
- **PAVEMENT EDGES (ON THE RIGHT- AND LEFT-HAND SIDE) ARE TO BE CHAMFERED DOWNWARD AT AN ANGLE OF 30 DEGREES AS SHOWN IN THE ATTACHED DIAGRAM.**
- **CONSTRUCTION OF ADDITIONAL PAVEMENT OF 8m x 6.7m x 0.18m IS TO BE PROVIDED FOR WITH THE SAME SPECIFICATION AS ABOVE EXCLUSIVE OF HARDCORE.**
- **8mm HIGH TENSION RODS ARE TO BE USED AS CONCRETE REINFORCEMENT.**

Job Terms:

- **QUOTATION IS SUBJECT TO 5% WHT.**
- **THERE WILL BE NO ADVANCE PAYMENT.**
- **BIDS ARE TO BE SUBMITTED ON OR BEFORE 11 AM - FRIDAY 13TH JANUARY 2022.**

NOTE:

BIDS ARE TO BE SUBMITTED ELECTRONICALLY THROUGH: lsfrfq@livestockfeedsplc.com

Signed:

Buying Committee Secretary

Buying Committee Chairman